



**NOTES:**

1. INSTALL SEDIMENT DAM ACCORDING TO MANUFACTURE'S RECOMMENDATION. ENDS SHALL NOT EXTEND BEYOND THE MOUNT OF THE INLET.
2. SEDIMENT DAMS ARE REQUIRED TO BE ACCOMPANIED BY ADDITIONAL BMPS TO PREVENT THE POTENTIAL OF SEDIMENTS ENTERING PROJECT STORM SYSTEMS.
3. INSPECTION & MAINTENANCE:
  - 3.1. INSPECT DAMS WEEKLY AND DAILY DURING STORM EVENTS.
  - 3.2. CLEAN, OR REPLACE, DAMS WHEN DEBRIS HAS REACH A HEIGHT OF 2 INCHES.
  - 3.3. CONTRACTOR IS RESPONSIBLE FOR REMOVING DAMS AND PROPERLY DISPOSING OF ALL MATERIALS ONCE THE PROJECT HAS BEEN PERMANENTLY STABILIZED.

DRAWN CJH	
DIV EROSION	
REV	DATE



**CITY OF BEND**  
 STANDARD DRAWING  
 710 NW WALL ST., BEND, OREGON 97701

---

**CURB INLET PROTECTION**

SCALE NTS
DATE 11/01/2024
APPR
STD DWG E-2A